

53 Stagecoach Rd.

C/S 1/03
DVP Plans ON
2) SENT PLANS TO John Hopwood
MAY 20, 2003

FORM 1A - APPLICATION FOR DSCP

No. 03-06

Fee 275⁰⁰ PD
ch# 1053

COMMONWEALTH OF MASSACHUSETTS
Board of Health, Amherst, MA.

APPLICATION FOR DISPOSAL SYSTEM CONSTRUCTION PERMIT

Application for a permit to: Construct () Repair (X) Upgrade () Abandon ()

Complete System

Individual Components

Location <u>53 Stagecoach Road</u>	Owner's Name <u>Richard Segool</u>
Map/Parcel # <u>30 B / 88</u>	Address <u>53 Stagecoach Road</u>
Lot #	Telephone # <u>413/253-7744</u>
Installer's Name	Designer's Name <u>Innovative Engineering</u>
Address	Address <u>110 Chapin Greene Dr., Ludlow</u>
Telephone #	Telephone # <u>413/583-7930</u>

Type of Building: Family dwelling, single

Lot size 30500 sq. ft.

Dwelling - No. of Bedrooms 3

Garbage grinder (no)

Other - Type of Building _____ No. of persons 6 Showers (1), Cafeteria ()

Other Fixtures

Design Flow (min. required) 330 gpd, Calculated design flow 330 gpd, Design flow provided 373 gpd

Plan: Date 01-May-03 Number of sheets 11 Revision Date

Title Sewage disposal system

Description of Soil(s) friable, firm in place

Soil Evaluator Form No. 11, Name of Soil Evaluator David Kopacz, Sr. Date of Soil Evaluation 29-Apr-03

DESCRIPTION OF REPAIRS OR ALTERATIONS

The undersigned agrees to install the above described Individual Sewage Disposal System in accordance with the provisions of

Title 5 and further agrees to not to place the system in operation until a Certificate of Compliance has been issued by the

Board of Health.

Signed [Signature]

Date 01-May-03

Inspections

SEWAGE DISPOSAL SYSTEM

AT

**53 STAGECOACH ROAD
AMHERST**

FOR

**RICHARD SEGOOL
53 STAGECOACH ROAD
AMHERST, MA 01002**

BY

**INNOVATIVE ENGINEERING
110 CHAPIN GREENE DRIVE
LUDLOW, MA 01056
PHONE: 413/583-7930
FAX: 413/583-8771**



John A. Kopinsky
02 - May '03

Index

Sheet 1	Title page
Sheet 2	Index
Sheet 3	USGS map
Sheet 4	Calculation sheet
Sheet 5	Distribution box specifications
Sheet 6	Septic tank specifications
Sheet 7	Title 5 fill specifications
Sheet 8	Pipe and baffle specifications
Sheet 9	Soil evaluation report
Sheet 10	Plan sheet - topo
Sheet 11	Plan sheet - system profile

Innovative Engineering

***110 Chapin Greene Drive
Ludlow, MA 01056***

Phone: 413/583-7930

FAX: 413/583-8771

**Richard Segool
53 Stagecoach Road
Amherst, MA 01002**


Project # : 030401

01-May-03

Scale : none

Sheet # 2 of 11

Project location



USGS Map

Innovative Engineering
*110 Chapin Greene Drive
Ludlow, MA 01056*

*Phone: 413/583-7930
FAX: 413/583-8771*

Richard Segool
53 Stagecoach Road
Amherst, MA 01002

Project # : 030401

01-May-03

Scale : none

Sheet # 3 of 11

Septic System Design Calculations - Field (Bed)

Location: *53 Stagecoach Road*

Town: *Amherst*

Property Owner: *Richard Segool*

53 Stagecoach Road

Amherst, MA 01002

Basic Data

Percolation Rate: *1.3 min. / inch*

Soil Texture: *loamy sand*

Soil Class: *I*

Effluent Loading Rate: *0.74 gpd / sf = A*

Number of bedrooms: *3 = B*

Is a garbage disposal to be installed? *no* (Yes / No)

System Sewage Flow

$$B \quad \underline{3} \quad \times \quad 110 \text{ gpd / bedroom} = \quad \underline{330} \text{ gpd} = C$$

Septic Tank Size

$$C \quad \underline{330} \quad \times 2 = \quad \underline{660} \text{ gallons} = D$$

If D is less than 1500 gallons, use 1500 gallon minimum size

If D is greater than 1500 gallons, use D as minimum size

Use 1500 gallon septic tank (minimum size)

Field Calculations

Width of field: 14 feet, Length of field: 36 feet, Stone depth below pipe invert (in): 6

Leaching (bottom) area of field: 504 sf = G

Soil Absorption System Capacity

$$G \quad \underline{504} \quad \times A \quad \underline{0.74} \quad = \quad \underline{373} \text{ gpd} = L$$

Summary

If no garbage disposal is to be installed, L 373 gpd must be equal or greater than C 330

If a garbage disposal is to be installed, L 373 gpd must be equal or greater than 1.5 x C 495


Calculations by: _____

Date: 01-May-03

Sheet #	4	of	11
---------	---	----	----

Distribution box

PROD #	A	B	C
DB-5	1'-3"	5"	4"



DESIGN NOTES

1. Concrete - 4000 p.s.i., 28 days

Innovative Engineering

**110 Chapin Greene Drive
Ludlow, MA 01056**

Phone: 413/583-7930

FAX: 413/583-8771

Richard Segool

**53 Stagecoach Road
Amherst, MA 01002**

Project # : 030401



01-May-03

Scale : none

Sheet # 5 of 11

Septic Tank

PROD #	A	B	C	D	E
AC-6-1500	7'-0"	9'-4"	6'-0"	4'-9"	1'-8"



Design Notes

1. Concrete - 4500 psi. 28 days
2. Reinforcement - ASTM A-615, Grade 60
3. Loading AASHTO HS10-44
4. Joints sealed with mastic sealant
5. Install gas baffle on outlet tee *Schd 40 Pipe*

Innovative Engineering
 110 Chapin Greene Drive
 Ludlow, MA 01056

Phone: 413/583-7930

FAX: 413/583-8771

Richard Segool
 53 Stagecoach Road
 Amherst, MA 01002

Project #: 030401

01-May-03

Scale: none

Sheet # 6 of 11

Title 5 Requirements for Fill & Leaching Aggregate

Fill

Fill material shall be clean granular sand, free from organic matter and shall not contain any material larger than 2 inches in size. The fill material shall meet the following gradation requirements:

<u>Sieve size</u>	<u>Percent passing</u>
#4	100
#50	10 - 100
#100	0 - 20
#200	0 - 5

Leaching aggregate

Base aggregate shall be 3/4" to 1-1/2" in diameter and shall be double-washed and free of iron, fines and dust (in place). The base aggregate shall extend from the bottom of the leach trench to the top of the distribution line. The upper layer of aggregate shall be 1/8" to 1/2" in diameter and shall be double washed and free from iron, fines and dust (in place). The upper aggregate layer shall be placed over the base aggregate to prevent intrusion of fine textured soils into the leaching system. Only approved Title 5 aggregates shall be incorporated in to this system.

Innovative Engineering
110 Chapin Greene Drive
Ludlow, MA 01056

Phone: 413/583-7930

FAX: 413/583-8771


Richard Segool
53 Stagecoach Road
Amherst, MA 01002

Project # : 030401

01-May-03

Scale : none

Sheet # 7 of 11



Pipe & Baffle Specifications

1. Pipe installed between the building and the septic tank shall be sch40 PVC and shall be installed at a minimum slope of 0.02 ft per ft.
2. Pipe installed between the septic tank and distribution box shall be sch40 PVC and shall be installed at a minimum slope of 0.02 ft. per ft.
3. Pipe exiting the distribution box shall be SDR35 and shall be installed level for the first two (2) feet minimum. Thereafter, the pipe shall be installed at a slope of 0.005 ft. per ft. and shall be perforated only in the leaching area
4. Leach trenches exceeding 50 ft. in length shall be connected and vented in accordance with the requirements of 310 CMR 15.241
5. Septic tank baffles shall be constructed from sch40 PVC pipe & fittings and shall extend a minimum of 6" above the flow line of the septic tank. Baffles shall be located beneath the tank clean-outs and within 12" of each end of the tank. There shall be a minimum 3" air space between the top of the baffle and the underside of the top of the tank. The inlet baffle shall extend a minimum of 10" below the tank flow line and the outlet baffle shall extend below the tank flow line in accordance with the following table:

<u>Liquid depth in tank</u>	<u>Depth of baffle below flow line</u>
4 ft.	14 in.
5 ft.	19 in.
6 ft.	24 in.
7 ft.	29 in.
8 ft.	34 in.

Innovative Engineering

***110 Chapin Greene Drive
Ludlow, MA 01056***

Phone: 413/583-7930

FAX: 413/583-8771


**Richard Segool
53 Stagecoach Road
Amherst, MA 01002**

Project # : 030401

01-May-03

Scale : none

Sheet # 8 of 11



Soil Evaluation Report

Form 11 - Soil Evaluation Form with attachments as follows :

- 1) Soil suitability assessment
- 2) On-site Review sheets
- 3) Determination for Seasonal High Water Table

Form 12 - Percolation Test

Innovative Engineering

***110 Chapin Greene Drive
Ludlow, MA 01056***

Phone: 413/583-7930

FAX: 413/583-8771


Richard Segool
53 Stagecoach Road
Amherst, MA 01002

Project # : 030401

01-May-03

Scale = none

Sheet # 9 of 11



FORM 11 - SOIL EVALUATOR FORM
Page 1 of 3

No. 1Date: 4-29-03

Commonwealth of Massachusetts
, Massachusetts

Soil Suitability Assessment for On-site Sewage Disposal

Performed By: David Kolacz SR
Witnessed By: David Zarozinski

Date: 4-29-03

Location Address or Map # & Lot #	<u>53 Stagecoach Rd Amherst MA, 01002</u>	Owner's Name:	<u>Richard Segool</u>
		Address:	<u>249 Fairhill Lane Suffield CT 06078</u>
		Telephone #:	<u>06078</u>
New Construction <input type="checkbox"/> Repair <input checked="" type="checkbox"/>			

Office Review

Published Soil Survey Available: No Yes

Year Published 1981 Publication Scale 1:15,840 Soil Map Unit HqB

Drainage Class excessively
degraded Soil Limitations _____

Surficial Geology Report Available: No Yes

Year Published _____ Publication Scale _____

Geologic Material (Map Unit) _____

Landform _____

Flood Insurance Rate Map:

Above 500 year flood boundary No Yes

Within 500 year flood boundary No Yes

Within 100 year flood boundary No Yes

Wetland Area:


National Wetland Inventory Map (map unit) _____

Wetlands Conservancy Program Map (map unit) _____

Current Water Resource Conditions (USGS): Month

Range: Above Normal Normal Below Normal

Other References Reviewed: _____



Location, Address, or Lot No. 53 Stagecoach Rd, AmherstOn-site ReviewDeep Hole Number 1 Date: 4-29-03 Time: 8:30 Weather Hazy/Sunny

Location (identify on site plan)

Land Use Residential Slope (%) 0-3 Surface Stones none observedVegetation LawnLandform Outwash Plain

Position on landscape (sketch on the back)

Distance from:

Open Water Body	> 200 feet	Drainage Way	> 100 feet
Possible Wet Area	> 100 feet	Property Line	80 feet
Drinking Water Well	> 100 feet	Other	feet

DEEP OBSERVATION HOLE LOG

Depth from Surface (inches)	Soil Horizon	Soil Texture (USGS)	Soil Color (Munsell)	Soil Mottling	Other (Structure, Stones, Boulders, Consistency, % Gravel)
0-16	A _p	LS	10YR 3/3		
16-46	B _{1c}	LS	7.5YR 4/4		Friable, loose Gravelly, 40-60% cobble
46-74	C ₁	LS	7.5YR 4/4	2.5Y 5/1	Friable, Dec roots, some cobble, loose in hand firm in place,
74-120	C ₂	UMLS	10YR 5/6	2.5YR 4/4 @74"	no cobble/stone firm in hand firm in place

* MINIMUM OF 2 HOLES REQUIRED AT EVERY PROPOSED DISPOSAL AREA

Parent Material (geologic) Outwash Depth To Bedrock: > 120"Depth to Groundwater: Standing Water in Hole: 112" Weeping from Pit Face: 92"Estimated Seasonal High Ground Water: 74"



FORM 12 - PERCOLATION TEST

Location Address or Lot No. 53 Stagecoach Rd, Amherst


COMMONWEALTH OF MASSACHUSETTS

Amherst, Massachusetts

Percolation Test		
Date:	<u>4-29-03</u>	Time: <u>8:45</u>
Observation Hole #	<u>1</u>	
Depth of Perc	<u>77"</u>	
Start Pre-soak	<u>8:58</u>	
End Pre-soak	<u>9:13</u>	
Time at 12"	<u>9:13</u>	
Time at 9"	<u>9:17</u>	
Time at 6"	<u>9:21</u>	
Time (9"-6")		
Rate Min./inch	<u>1.2 min/in</u>	

- Minimum of 1 percolation test must be performed in both the primary area AND reserve area.

Site Passed Site Failed Performed By: David Kofacz SAWitnessed By: David ZarozinskiComments: 3 Bedroom, Remove Garbage Grinder, 5' Separation to GU



Location Address or Lot No. 53 Stagecoach Rd, Amherst**Determination for Seasonal High Ground Water Table****Method Used:**

- Depth observed standing in observation hole 112 inches
 Depth weeping from side of observation hole 92 inches
 Depth to soil mottles 24 inches
 Ground water adjustment _____ feet

Index Well Number

Reading Date

Index Well level

Adjustment factor

Adjustment ground water level

Depth of Naturally Occurring Pervious Material


Does at least four feet of naturally occurring pervious material exist in all areas observed throughout the area proposed for the soil absorption system? yes


If not, what is the depth of naturally occurring pervious material? _____

Certification


I certify that on Spring 97 (date) I have passed the soil evaluator examination approved by the Department of Environmental Protection and that the above analysis was performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017.

Signature D. J. King Jr. Date 4-29-03





Richard Segor



1053

TOWN OF AMHERST
HEALTH PERMITS/INSPECTION SERVICES

No. 2222

Received of AMERICAN CONSULTING & ENVIRONMENTAL SERVICES of P.O. Box 158 Belchertown MA.
Name Address 01007
323-0904

For Property Located at: 53 Stagecoach Rd Howard Segool
Street Address Owner

- | | |
|--|---|
| HEA009 Bakery _____
R6510 443508 | HEA015 Sanitary Code Booklets _____
R6510 432305 |
| HEA001 Bed & Breakfast _____
R6510 443516 | HEA016 Septic Tank Permit-Installers _____
R6510 443511 |
| HEA002 Catering License _____
R6510 443507 | HEA017 Septic Tank Permit-Private <u>(1) 100.00</u>
R6510 443510 |
| HEA003 Food Handler _____
R6510 443515 | HEA018 Septic Tank Reinspection Fee _____
R6510 432301 |
| HEA004 Frozen Deserts _____
R6510 443501 | HEA019 Sub-Division Review Fee _____
R6510 432306 |
| HEA005 Health Dept. Housing Isp. _____
R6510 432302 | HEA012 Swimming Pool Permits _____
R6510 443512 |
| HEA006 Massage Therapy License _____
R6510 443504 | HEA020 Tanning License _____
R6510 443509 |
| HEA007 Milk & Cream License _____
R6510 443500 | HEA024 Funeral Director License _____
R6510 443502 |
| HEA008 Motel License _____
R6510 443506 | HEA034 Immunization Clinic _____
R6510 432307 |
| HEA010 Removal of Offal _____
R6510 443513 | HEA030 Car Seats _____
8407 258004 |
| HEA021 Removal of Rubbish _____
R6510 443520 | HEA026 Smoking & Tobacco Reg. Violations _____
R6510 443518 |
| HEA011 Percolation Test Fees <u>(1) 175.00</u>
R6510 432300 | HEA023 TB Clinic _____
R6510 432303 |
| HEA013 Recreation Camp License _____
R6510 443503 | HEA022 Tobacco License _____
R6510 443505 |
| HEA014 Retail Store Permit _____
R6510 443514 | HEA _____ |
| | HEA _____ |

TOTAL FEE: 275.00
Date 4/29/03

[Signature]
Inspector Services/Health Department

Security enhanced document. See back for details.

AMERICAN CONSULTING & ENVIRONMENTAL SERVICES
DEP CERTIFIED
PO BOX 158 413-323-0904
BELCHERTOWN, MA 01007

1053
29-7003/2213
419

PAY TO THE ORDER OF Town of Amherst \$ 275.00
Two hundred seventy five Dollars and 00/100 DOLLARS


DATE 4-29-03

FOR 53 Stagecoach Rd, Amherst [Signature]

CHARTER ONE BANK Belchertown Branch
CHARTERONE.COM

MP

⑈001053⑈ ⑆221370030⑆ ⑆4190016638⑈



NO: _____

Town Water

275⁰⁰ P6-1033 CH
3 Bedrooms Remove a/c

Commonwealth of Massachusetts

Town of Amherst

Soil Suitability Assessment : On-Site Sewage Disposal

Performed By: DAVID KOPACZ Date: 4/29/03
Witnessed By: DAVID ZARZINSKI

Location Address of: Lot #	Owner's Name: <u>Howard Segool</u> Address of: <u>53 STAGECOACH RD</u> Telephone: <u>253-7744</u>
New Construction <input type="checkbox"/> Repair <input checked="" type="checkbox"/>	

Office Review

Published Soil Survey Available? No Yes
Year Published _____ Publication Scale _____ Soil Map Unit _____
Drainage Class _____ Soil Limitations _____

Surficial Geologic Report Available? No Yes
Year Published _____ Publication Scale _____
Geologic Material (map unit) _____
Landform _____

Flood Insurance Rate Map:
Above 500 year flood boundary? No Yes
Within 500 year flood boundary? No Yes
Within 100 year flood boundary? No Yes

Wetland Area:
National Wetland Inventory Map (map unit) _____
Wetlands Conservancy Program Map (map unit) _____

Current Water Resource Conditions (USGS): month _____
Range: Above Normal Normal Below Normal

Other Reference Reviewed:

Determination: Seasonal High Water Table

Methods Used:

- Depth observed standing in observation hole _____ inches
- Depth weeping from side of observation hole _____ inches
- Depth to soil mottles _____ inches
- Ground water adjustment _____ feet

Index Well No. _____ Reading Date _____ Index Well Level _____
Adjustment factor _____ Adjusted ground water level _____

Depth of Naturally Occurring Previous Material


Does at least four feet of naturally occurring previous materials exist in all areas observed throughout the area proposed for this soil absorption system? _____

If not, what is the depth of naturally occurring previous material?

Certification

I certify that on _____ (date) I have passed the soil evaluator examination approved by the Department of Environmental Protection and that the above analysis was performed by me consistent with the required training, expertise, and experience described in 310 CMR 15.017.

Signature _____
Date _____



REPAIR 53 STAFFCOACH RD

On-Site Review

Deep Hole Number ① Date: 4/29/03 Time _____
 Weather Sunny 70's
 Location (identify on site plan) _____
 Land Use Residential Slope (%) 0-3
 Surface Stone None
 Vegetation: Lawn

Landform: _____

outwash plain

Position on Landscape (sketch on back) _____

Distances from:

Open Water Body 100 feet Drainageway 100 feet
 Possible Wet Area 100 feet Property Line 80 feet
 Drinking Water Well 100 feet Other _____

DEEP OBSERVATION HOLE LOG

depth from surface (inches)	soil horizon	soil texture (USDA)	soil color (Munsell)	soil mottling	other (structure, stones, boulders) Consistency, % gravel
16	A _p	LS	10YR 3/3		
46	B _c	LS	7.5YR 4/4	74" 2.5YR 5/1	Gravel lens 40-60% BBH
74	C ₁	LS	7.5YR 4/4	2.5YR 4/6	knobby Deep Root Loosening
120	C ₂	Fine LS	10YR 5/6		16-24" hard firm in place

Parent Material (geologic) OUTWASH
 Depth to Bedrock 120+
 Depth to Groundwater:
 Standing Water in the Hole 112"
 Weeping from Pit Face 92"
 Estimated Seasonal High Water 74"

On-Site Review

Deep Hole Number _____ Date: _____ Time _____
 Weather _____
 Location (identify on site plan) _____
 Land Use _____ Slope (%) _____
 Surface Stone _____
 Vegetation: _____

Landform: _____

Position on Landscape (sketch on back) _____


Distances from:

Open Water Body _____ feet Drainageway _____ feet
 Possible Wet Area _____ feet Property Line _____ feet
 Drinking Water Well _____ feet Other _____

DEEP OBSERVATION HOLE LOG

depth from surface (inches)	soil horizon	soil texture (USDA)	soil color (Munsell)	soil mottling	other (structure, stones, boulders) Consistency, % gravel

Parent Material (geologic) _____
 Depth to Bedrock _____
 Depth to Groundwater:
 Standing Water in the Hole _____
 Weeping from Pit Face _____
 Estimated Seasonal High Water _____



LOT LINE



← 83' ant →

3 Bedrooms
Remove R/G.

Arrowhead Drive

Town Water

FORM 12: Percolation Test
Location Address or Lot # 53 Stagecoach Road

Commonwealth of Massachusetts
Town of Amherst

PERCOLATION TEST *		
DATE: <u>4/29/13</u>		TIME:
Observation Hole #	<u>(1)</u>	
Depth of Perc	<u>77"</u>	
Start Pre-soak	<u>8:58</u>	
End Pre-soak	<u>9:13</u>	
Time at 12"	<u>9:13</u>	
Time at 9"	<u>9:17</u>	
Time at 6"	<u>9:21</u>	
Time (9"-6")	<u>4</u>	
Rate Min./Inch	<u>72</u>	

*Minimum of one percolation test must be performed in both the primary area and reserve area.


Site Passed Site failed


Performed by David Kopacz

Witnessed by David Zarowski

Comments:

Stage Coach Rd






53 Stagecoach Road perc test 4/29/03
Engineer: David Kopacz
Owner: Howard Segool

The first part of the document discusses the importance of maintaining accurate records of all transactions. It emphasizes that every entry should be supported by a valid receipt or invoice. This not only helps in tracking expenses but also ensures compliance with tax regulations.


In the second section, the author outlines the various methods used for data collection and analysis. These include surveys, interviews, and focus groups. Each method has its own strengths and weaknesses, and the choice of method depends on the specific research objectives.


The third section provides a detailed overview of the results obtained from the study. It highlights the key findings and discusses their implications for the industry. The data shows a clear trend towards digitalization, with a significant increase in online transactions over the past few years.

Finally, the document concludes with a series of recommendations for future research and practice. It suggests that further exploration is needed in the area of digital marketing strategies and their impact on consumer behavior.



Perc test 53 Stagecoach Road 4/29/03
Engineer: David Kopacz
Owner: Howard Segool





NOTES

General

All work to be done in accordance with 310 CMR 15.000
 TBM = 100.00' - top of concrete bound in NE corner of lot
 Existing components shown in green, proposed in blue and reserve in red
 Existing contours shown dashed, proposed contours shown solid

Septic tank

Remove & dispose of existing septic tank structure
 Connect to relocated outlet pipe from house - invert elev 105.84' at septic tank
 All plumbing shall be in accordance with the Massachusetts Plumbing Code
 Maintain minimum 10' separation distance from existing foundation wall

Leach bed

Remove all "A" and "B" horizon soils in leach bed area prior to placing approved Title 5 fill
 See attached soil sheets - Section 9 for limits of "A" & "B" horizons
 Finish grade over leach bed = 106.45'
 Maintain minimum 20' separation distance from existing foundation wall


Maintenance

Septic tank shall be pumped in accordance with 310 CMR 15.351 - recommended on an annual basis or, at a minimum, once every three years

Misc. Notes


No existing wells within 200'
 No variances required
 Existing garbage grinder shall be removed prior to acceptance of system


Innovative Engineering
 110 Chapin Greene Drive
 Ludlow, MA 01056
 Phone: 413/583-7930
 FAX: 413/583-8771




Project # 030401
Date : 01-May-03
Scale : 1" = 30'
Designed by : JAK
Checked by : JAK

Proposed Sub-surface Sewage Disposal System for :		
Richard Segool		
53 Stagecoach Road		
Amherst, MA 01002		
Revision no. 1	Dated: 14-May-03	Sheet # 10 of 11





System Profile



Leach Bed Cross-section

NOTES

1. TBM1 = 100.00' (top of concrete bound in NE corner of property)
2. Remove all "A" and "B" soil horizons prior to placing approved Title 5 fill (see fill specifications)
3. Septic tank and d-box to be installed level and true to grade on min. 6" base of compacted 3/4" to 1-1/2" stone
4. All work to be completed in accordance with 310 CMR 15.000
5. Existing garbage grinder shall be removed prior to acceptance of system
6. Plumbing modifications inside house, required to meet proposed grade of new system, shall be done in accordance with Mass. Plumbing Code
7. Existing septic tank to be removed and disposed of properly in accordance with 310 CMR 15.354(3)(c)

Innovative Engineering
 110 Chapin Greene Drive
 Ludlow, MA 01056
 Phone: 413/583-7930
 FAX: 413/583-8771



Project #	030401
Date :	01-May-03
Scale :	none
Designed by :	JAK
Checked by :	JAK

Proposed Sub-surface Sewage Disposal System for :		
Richard Segool 53 Stagecoach Road Amherst, MA 01002		
Revision no. 1	Dated: 14-May-03	Sheet # 11 of 11

